

Overview and Status of the Austrian Particle Therapy Facility MedAustron

Peter Urschütz



MedAustron

- Centre for ion beam therapy and non-clinical research
- Treatment of 1200 patients/year in full operation
- Worldwide the 6th combined centre for ion beam therapy with protons and carbon ions
- Founded in 2007 as „EBG MedAustron GmbH“
 - in indirect ownership of the federal state of Lower Austria

Financing

- Investment volume: € 200 million

- Financing partners:
 - Republic of Austria
 - Federal State of Lower Austria
 - City of Wr. Neustadt

Location

- Wiener Neustadt, approx. 50 km southern of Vienna
- 40.000 inhabitants



Radiotherapy

Conventional Radiotherapy

Accelerator type




Particle type

Austria

World

Proton Therapy

Accelerator type




Particle type

Austria

World

Ion Therapy

Accelerator type



Particle type

Austria


World

Ion beam therapy – innovative form of radiotherapy


Main benefit: protection of surrounding healthy tissue.

Treatment of tumors next to **organs at risk**

Huge benefit specially for **kids**.



Carbon ions – differences compared to protons




- Higher and energy dependent LET
- Higher and energy dependent RBE
- Less scattering
- Lower dependency on the cell cycle
- Increased effectiveness in case of radiation resistant tumor (hypoxic tumors)
- Improved dose conformity
- Potentially lower fractionation scheme
- Increased fragmentation tail
- Less experience compared to protons
- Lower acceptance in the community


The MedAustron facility



Irradiation room configuration



Irradiation concept




- active energy selection
- > penetration depth
- transverse pencil beam scanning
- online beam monitoring




Courtesy of GSI

- no patient specific passive devices!


Source room




- Ion sources to produce protons or carbon ions
- Back-up source



Linear accelerator




- Pre-acceleration and beam shaping to meet injection conditions of synchrotron




The Injector

- Generation of protons and C^{6+}
- Acceleration of beam to 7 MeV/u



Synchrotron


Beam from Injector (7 MeV/u)



- Acceleration of beams to desired extraction energy
- Active energy selection:
 - 255 selectable energy steps (steps of 1 – 2 mm)
 - p: 60 – 250 MeV (NCR: 800 MeV)
 - C: 120 – 400 MeV/u
- Ramp speed: 0.5 s to highest energy
- Extraction time: 1 – 10 s


The synchrotron

Center-piece of the accelerator



Synchrotron


Typical cycle for a synchrotron for medical use with slow extraction.



- Beam structure: pulsed, energy and intensity variable

Synchrotron hall







Extraction line

guiding the beam
into the 4 irradiation rooms

Scanning System



- Transverse pencil beam scanning:
beam size: mm range (FWHM in vacuum)
- Fast magnetic deflection:
scanning speed > 20 m/s
- One iso-energy slice irradiated with
approx. one extracted beam pulse (spill of
1 – 10 s)



Particle accelerator – key figures

- developed in close cooperation with CERN
- more than 1.000 large components
- 220 manufacturers from 23 countries
- diameter of the synchrotron: 25 m
- more than 100 km of cables
- power consumption: 5 MW (approx. 10.000 households)

Beam parameters

—● Particles

- protons, carbon ions

—● Energy

- Clinical energies: p: 60-250 MeV; C6+: 120-400 MeV/u -> **3-37 (p) / 27 (C) cm penetration depth in water**
- IR1: clinical energies + up to 800 MeV for protons

—● Intensity

- Per spill: $1 * 10^{10}$ (p) / $4 * 10^8$ (C)
- 4 different intensity levels

—● Size

- 4 sizes: 4, 6, 8, 10 mm FWHM [in vacuum]
- Scanning field : 20x20 cm² (IR1-3), 12x20 cm² (IR4)

—● Beam delivery precision


- < 0.5 mm

100.000 different beam combinations...

Accelerator is able to generate:

- 2 ion species
 - 255 different energies
 - 4 beam sizes
 - 4 intensities
 - 8 extraction lengths
- 65'280 Beam combinations per beam line
- Gantry: various angles need to be considered
- Non-clinical research: extended energy range

⇒ huge amount of commissioning work



The screenshot shows the 'LIBC - Auswahl' window. It features a large grid of energy values (1 to 296) and three vertical columns for 'Extr', 'Focus', and 'Int'. The 'Focus' column has '1' selected for energy 296. Below the grid is a summary table:

Parameter	Index	Wert
Ion Type	3	P
Energy	296	221.07 MeV/u
Focus	1	8.10 mm
Intensity	13	2.6E009 Teilchen/s
Extraction	3	8 s

Buttons for 'Setzen' and 'Abbrechen' are located at the bottom right of the window.


Example for table to select a beam combination

Comparison Synchrotron - Cyclotron

- Energy: **active energy selection** vs. fixed energy (+ degrader)
- Radiation protection: **small** vs. large efforts
- Beam currents: low vs. **high**
- Ion species: **multiple ions** vs. protons only
- Footprint: large vs. **small**
- Cost: high vs. **low**
- Vendors: no commercial systems (Europe) vs. **multiple vendors**

The proton gantry

- rotating the beam 180° around the patient
- allows irradiation from various angles
- based on the PSI-2-Gantry, further developed by MedAustron
- total weight: 220 t
- swing diameter: 7,5 m
- precision: $< 0,1^\circ$
- isocentre: $< 0,3$ mm





The proton gantry



Gantry treatment room




CE labelled medical product



CE according to Medical Device Directive (MDD)


Irradiation room



- Patient treatment is controlled and monitored by the Oncology Information System (OIS)

Robotic patient positioning system

- ceiling-mounted
- 7 degrees of freedom
- non-isocentric treatment
- tracking position of the bench with optical tracking system
- positioning accuracy: < 0.5 mm



Patient position verification system

- Flat panel and X-ray tube rotatable around the ring, couchmounted
- fast flat panel detector (30 Hz framerate)
- single source dual energy X-ray (60, 120 kV)
- large clearance (78 cm ring)
- 2D, 3D imaging
- cone beam CT



Patient positioning and verification system



MedAustron: project timeline and status



Construction 2011- 2012 (18 months)



Construction 2011- 2012 (18 months)




Oct 2012: Moving in



Accelerator installation 2013 - 2014




**First beam in IR3
in Oct. 2014**





Accelerator commissioning 2015

- work in progress
- intensity, beam position and FWHM beam size over extracted spill measured in HEBT




CC	004440441009026C
VACC	na
BS	2015100810082200-6
noiseth.	2.0 %
analimit	10.0 %
IID	0
SID	0

exp.time	19.999999552965164 ms
framerate	25 f/s
trigger	StartExtraction
date	2015-10-08 08:12:45.629585
intensity	8e6 arb.u.
CoGw	2.3 ± 0.1 mm [2.0, 2.5]
FWHM	19.5 ± 0.8 mm [16.7, 20.6]




Accelerator commissioning 2015

- work in progress
- beam measured by detectors of dose delivery system




Penetration depth



● Particle energy successfully adjusted within a single iteration round.


Beam size




- measured at isocenter
- beam size and symmetry adjusted within a single iteration round.

Recent commissioning results

250 MeV Scanned Proton



FWHM x: 7.0 mm
FWHM y: 7.0 mm




Recent commissioning results

250 MeV Scanned Proton




FWHM x: 7.0 mm
FWHM y: 7.0 mm



Installation of vertical beam line

- Vertical beam line installed in Q4 2015
- Beam commissioning in 2017



Remaining steps towards 1st patient treatment

- Finalisation of the proton beam commissioning for horizontal fixed beam lines
 - Fine tuning of beams
 - Coverage of full parameter space (different energies, intensities, etc...)
- System integration (complete workflow)
- Interlock and error management
- Verification and validation test phase
- Technical documentation and regulatory aspects
- Medical physics: base data measurements (TPS)
- End to end tests

1st patient treatment in 2016

- 2016: first patient treatment with protons (horizontal fixed beam lines)
- 2016: provide beams for non clinical research
- 2017 – 20:
 - Commissioning of further beam lines,
 - Carbon ions,
 - Gantry
 - enhance functionalities, performance increase
- 2020/21: full operation

Thank you for your
attention!

