


# ESRF EBS Accelerator Upgrade

PSI, January 18<sup>th</sup> 2016

**Pantaleo Raimondi**

*On behalf of the Accelerator Project Phase II Team*



**ESRF**

| The European Synchrotron



The Accelerator Upgrade Phase II aims to:


- Substantially decrease the Store Ring Equilibrium Horizontal Emittance
- Increase the source brilliance
- Increase its coherent fraction

*In the context of the R&D on “Ultimate Storage Ring”, the ESRF has developed a solution, based on the following requirements and constraints:*

- Reduce the horizontal equilibrium emittance from 4 nm to less than 140 pm
- Maintain the existing ID straights beamlines
- Maintain the existing bending magnet beamlines
- Preserve the time structure operation and a multibunch current of 200 mA
- Keep the present injector complex
- Reuse, as much as possible, existing hardware
- Minimize the energy lost in synchrotron radiation
- Minimize operation costs, particularly wall-plug power
- Limit the downtime for installation and commissioning to less than 18 months.


**Maintain standard User-Mode Operations until  
the day of shut-down for installation**

# LOW EMITTANCE RINGS TREND



# BRILLIANCE AND COHERENCE INCREASE


## Brilliance




Hor. Emittance [nm]	4	0.135
Vert. Emittance [pm]	4	5
Energy spread [%]	0.1	0.09
$\beta_x[\text{m}]/\beta_z[\text{m}]$	37/3	6.9/2.6

Source performances will improve by a factor 50 to 100

## 18mm Undulator spectrum



Undulator  
:



## Coherence

# BENDING MAGNETS SOURCE: 2-POLE, 3-POLE OR SHORT WIGGLERS

All new projects of diffraction limited storage rings have to deal with:



Increased number of bending magnets / cell => BM field reduction

Conflict with hard X-ray demand from BM beamlines

ESRF will go from 0.85 T BM to 0.54 T BM


The BM Sources will be replaced by dedicated 2-Pole or 3-Pole Wigglers

- Field Customized
- Large fan with flat top field
- 2 mrad feasible for 1.1 T 3PW
- Mechanical length  $\leq 150$  mm
- Source shifts longitudinally by  $\sim 3$ m
- Source shifts horizontally by  $\sim 1$ -2cm






# ESRF Phase II Upgrade at the Bone



Present ESRF Arc Layout:  $E_x=4\text{nm}$



New Low Emittance Layout:  $E_x=0.135\text{nm}$


The 844m Accelerator ring consists of:

- 32 identical Arcs 21.2m long
- 32 straight sections 5.2m long equipped with undulators and RF

Each Arc is composed by a well defined sequence of Magnets (dipoles, quadrupoles etc), Vacuum Components (vacuum vessel, vacuum pumps etc), Diagnostic (Beam Position Monitors etc) etc.

All the Arcs will be replaced by a completely new Layout

# THE EVOLUTION TO MULTI-BEND LATTICE



## Double-Bend Achromat (DBA)



- Many 3<sup>rd</sup> gen. SR sources
- Local dispersion bump (originally closed) for chromaticity correction



# THE EVOLUTION TO MULTI-BEND LATTICE

## Double-Bend Achromat (DBA)

- Many 3<sup>rd</sup> gen. SR sources
- Local dispersion bump (originally closed) for chromaticity correction



## Multi-Bend Achromat (MBA)



- MAX IV and other USRs
- No dispersion bump, its value is a trade-off between emittance and sextupoles (DA)

# THE HYBRID MULTI-BEND (HMB) LATTICE

## ESRF existing (DBA) cell

- $E_x = 4 \text{ nm}\cdot\text{rad}$
- tunes (36.44, 13.39)
- nat. chromaticity (-130, -58)

**- Multi-bend for lower emittance**  
**- Dispersion bump for efficient chromaticity correction => "weak" sextupoles (<0.6kT/m)**  
**- Fewer sextupoles than in DBA**  
**- Longer and weaker dipoles => less SR**  
**- No need of "large" dispersion on the inner dipoles => small  $H_x$  and  $E_x$**



## Proposed HMB cell

- $E_x = 140 \text{ pm}\cdot\text{rad}$
- tunes (76.21, 27.34)
- nat. chromaticity (-99, -82)

# LINEAR AND NONLINEAR OPTIMIZATIONS

Linear and nonlinear optimizations have been done with the multi-objective genetic algorithm NSGA-II, to maximize Touschek lifetime and dynamic aperture.

Lifetime and dynamic aperture are computed on 10 different errors seeds.


Sextupoles: from 6 to 3 families, weaker and shorter.

Octupoles: from 2 to 1 family, weaker and shorter.

Tunes: 76.21 27.34



Linear matching parameters:  $\beta_{xID} = 6.9m$

Chromaticities: 6, 4



# LIFETIME OF S28B

s28b bpm0208nominal LOW EMIT RING INJ @S3. 512 turns WP 021 034 s28b bpm0208nominal 10  
 DA on en : -12.4 mm En. Acc. : -6.0 % T.L. : 45.1h I.E. : NaN% I.E. RF : NaN% I.E. rb : 100.0%  
 error average 10 seeds DA on en : -10.2 +/- 0.5 mm En. Acc. : -6.0 +/- 0.0 % T.L. : 23.0 +/- 1.3 h  
 I.E. : NaN +/- NaN % I.E. RF : NaN +/- NaN % I.E. rb : 97.9 +/- 1.1 %





**S28A**  
**DA -8.1mm@S3**  
**TLT ~ 13h.**

**S28B**  
**DA -10mm@S3**  
**TLT ~ 21h**



$e_y=5\mu\text{m}$	ESRF	Upgrade
Multibunch	64 h	21 h
16 bunch	6 h	2.1 h
4 bunch	4 h	1.4 h

# COLLIMATION OPTIMIZATION TO DECREASE LOSSES IN THE IDS

80% of the losses are relocated on the scrapers for 4% lifetime reduction:




*No scrapers*




*Two scrapers in  
DR\_37 of cells 13  
and 24*








ambient dose equivalent rate ( $\mu\text{Sv/h}$ )





## Several iterations made between:


- Optics optimization: general performances in terms of emittance, dynamic aperture, energy spread etc...
- Magnets requirements: fields, gradients...
- Vacuum system requirements: chambers, absorbers, pumping etc
- Diagnostic requirements
- Bending beam lines source

# Technical challenge: Magnets System

## Mechanical design final drawing phase


- Large positioning pins for opening repeatability
- Tight tolerances on pole profiles
- Prototypes delivered in the period September 2014-Spring 2015

Quadrupole  
Around  $52 \text{ Tm}^{-1}$



Octupoles

Sextupoles  
Length 200mm  
Gradient:  $3500 \text{ Tm}^{-2}$




Gael Le Bec




The European Synchrotron

ESRF




High gradient quadrupoles

- Gradient:  $90 \text{ T/m}$
- **Bore radius:  $12.5 \text{ mm}$**
- Length:  $390/490 \text{ mm}$
- Power:  $1-2 \text{ kW}$




Permanent magnet ( $\text{Sm}_2\text{Co}_{17}$ ) dipoles  
longitudinal gradient  $0.16 - 0.65 \text{ T}$ , magnetic gap  $25 \text{ mm}$   
 $1.8 \text{ meters long, 5 modules}$




Combined Dipole-Quadrupoles  
 $0.54 \text{ T} / 34 \text{ Tm}^{-1}$  &  $0.43 \text{ T} / 34 \text{ Tm}^{-1}$

## Pole shape optimization


*Imposed 11mm stay clear from pole to pole for all magnets for optimal synchrotron radiation handling*



Low gradient pole profile



High gradient pole profile



Vacuum chamber and magnets sections




# QUADRUPOLES

## High Gradient

- 91 T/m gradient, 388 – 484 mm length
- 12.7 mm bore radius, 11 mm vertical gap
- 1.4 – 1.6 kW power consumption


## HG Prototype

+/-20um pole accuracy



## Moderate Gradient

- Up to 58 T/m gradient, 162– 295 mm length
- 16.4 mm bore radius, 11 mm vertical gap
- 0.7 – 1.0 kW power consumption





# DIPOLE WITH LONGITUDINAL GRADIENT

## Specifications



- 0.17 – 0.67 T field
- 5 modules of 357 mm each
- Larger gap for the low field module
- Allows the installation of an absorber

## Engineering design

- Final drawings produced


## Prototyping

- Final prototype to be build in the coming months




Measured field integral homogeneity  
(one module)

# DIPOLE QUADRUPOLES




DQ1 pole shape



DQ1 gradient homogeneity:

**Integration of trajectory along an arc**



DQ1: 1.028 m, 0.57 T, 37.1 T/m

$\Delta G/G < 1\%$  (GFR radius 7 mm)



DQs are machined in 7 laminated iron plates

## S28b specifications

- 48 kT/m<sup>3</sup> nominal strength (70 kT/m<sup>3</sup> maximum)
- 90 mm length
- 4 Water cooled coils at the return-field yoke
- Allows for the required stay-clear for Synchrotron Radiation fans

## Prototyping

- Air cooled prototype measured



## Orange Book



Technical Design Study (TDS)  
Completed on May-2014  
and submitted to:

Science Advisory Committee (SAC)

Accelerator Project Advisory Committee  
(APAC)

Cost Review Panel (CRP)

ESRF Council

All committees very positive  
Project Approved and Funded  
Official Start: Jan 1<sup>st</sup> 2015

# PLANNING AND BUDGET

## Global Schedule

<i>Nov 2012</i>	White paper
<i>Nov 2012- Nov 2014</i>	Technical Design Study / Orange Book
<i>Jun 2014</i>	Council Approval
<i>Jan 2015</i>	Start of the project
<i>Jan 2015 – July 2016</i>	Engineering Design
<i>Jul 2015 – Jun 2018</i>	Procurement
<i>Sep 2017 – Oct 2018</i>	Girder Assembly
<i>Dec 2018</i>	Start of the shutdown
<i>Dec 2018 – Nov 2019</i>	Dismantling and Installation
<i>Dec 2019 – Jun 2020</i>	Accelerator and Beamlines Commissioning
<i>Jun 2020</i>	Start of User Mode Operations

### **Budget:**

**100 M€** Construction of the new storage ring lattice

**3.5 M€** Building programme for storage and pre-assembly




# STATUS PROGRESS: GENERAL

- **Project Organization and Project Management finalized**
- **WPs deliverables reviewed**
- **WPs budgets and spending profiles reviewed and finalized**
- **Master Schedule finalized**
- **Design phase nearly completed**
- **Procurement phase started**
- **Fully resource loaded Assembly Phase planning is ongoing**
- **Fully resource loaded Installation Phase planning is ongoing**
- **Staffing, CDI 100% completed, CDD/COD 75% complete**

**ASD extremely involved in all the phases  
All the other Divisions are fully committed  
as well**

# ORGANIZATION: ACCELERATOR PROJECT OFFICE



# ACCELERATOR PROJECT MANAGEMENT STRUCTURE

## Accelerator Project Office

WP-0  
**Management**  
P. Mackrill

WP-5 \*  
**Radio Frequency**  
J. Jacob

WP-10  
**Vacuum**  
M. Hahn

WP-1  
**Beam Dynamics**  
L. Farvacque

WP-6  
**Control System**  
J.-M. Chaize

WP-11  
**Buildings & Infrastructure**  
T. Marchial

WP-2  
**Magnets**  
G. LeBec

WP-7  
**Diagnostics & Feedbacks**  
K. Scheidt

WP-12  
**Reliability & Operation**  
L. Hardy

WP-3  
**Accelerator Engineering**  
J.-C. Biasci

WP-8  
**Photon Source**  
J. Chavanne

WP-13  
**Radiation Safety**  
P. Berkvens

WP-4 \*  
**Power Supply & Elec. Engineering**  
J.-F. Bouteille

WP-9 \*  
**Injector Upgrade**  
T. Perron

\* WP 4, 5 and 9 have both Phase I and Phase II deliverables (and budgets).

WP0, WP3, WP6, WP11, WP12, WP13 are highly transversal

# STATUS PROGRESS: DESIGN

➤ Design of all the components being finalized:

- Magnets ~95% (correctors, in progress)
- Vacuum System ~90% (one-of-a-kind chambers, in progress)
- Absorbers ~90%
- Girders ~100%
- Supports ~95%
- Diagnostics ~80% (Collimators, special chambers)
- Power Supplies ~80% (sizing optimization and hot-swap implementation)

➤ All elements have been fully integrated and are consistent with the overall specifications

**ISDD and TID very heavily involved for**

- Design finalization
- System integration
- Logistic

# STATUS PROGRESS: PROCUREMENT






- Pre-Qualifications of companies has been performed for magnets and vacuum chambers
- No other components do require PQs
- All contracts for magnets expected by Spring 2016 (2 contracts placed in 2015)
- All contracts for vacuum chambers expected by Spring 2016 (several CFTs already launched)
- Girders contract(s) expected by March 2016
- Infrastructure adaptations finalized, CFTs expected by March 2016
- All large scale procurements in place by mid 2016
- Delivery will start by the end of 2016 for about 2 years

**ADM very heavily involved for**  
- Budget and Financing  
- Procurement  
- Personnel




# PROCUREMENT: MAGNETS

More than 1000 Magnets to be procured by the end of 2018



196 sextupoles




100 correctors

Courtesy of ASD-IDM & ISDD-MEG

# PROCUREMENT: VACUUM CHAMBERS

Vacuum chambers: more than 450 chambers to be procured in less than 3 years



Courtesy of ASD-FE, ISDD-MEG & TID-VG



# 1000 LARGE POWER SUPPLIES AND 1000 SMALL POWER SUPPLIES

Type	Name	quantity per cell	NOMINAL FIELD VALUES			Electrical design PS				nom			maxWatt P total cell	
			Length [m]	dB/dx [T/m]	lattice	Power [kW]	Voltage [V]	Current [A]	OVdesign factor	Watts lmax	Watts Pnom	Watts Pmax		Watts cell
Quadrupole, mod. gradient	QF1	2	0.349	53.7		1.06	12.1	87.5	1.2	102	1167	1576	2334	3152
Quadrupole, mod. gradient	QD2	2	0.266	51.5		0.86	9.8	87.5	1.2	106	966	1418	1932	2836
Quadrupole, mod. gradient	QD3	2	0.216	46.5		0.74	8.4	87.5	1.2	117	843	1519	1687	3037
Quadrupole, mod. gradient	QF4	4	0.216	51.5		0.74	8.4	87.5	1.2	106	843	1238	3373	4952
Quadrupole, mod. gradient	QD5	2	0.212	52.5		0.86	9.8	87.5	1.2	104	966	1364	1932	2729
<b>Total</b>		<b>12</b>											<b>11257</b>	<b>16705</b>
Quadrupole, high gradient	QF6	2	0.36	95.2		1.42	15.7	90.4	1.1	99	1535	1857	3070	3714
Quadrupole, high gradient	QF8	2	0.48	96.2		1.66	18.6	89	1.1	98	1767	2139	3535	4277
<b>Total</b>		<b>4</b>											<b>6605</b>	<b>7992</b>
Dipole-Quadrupole, high field	DQ1	2	1.11	37.54	33.9	1.59	15.75	100.7	1.2	121	1729	2490	3458	4980
Dipole-Quadrupole, mod field	DQ2	1	0.77	37.04	33.7	1.38	17.0	81.0	1.2	97	1469	2116	1469	2116
<b>Total</b>		<b>3</b>											<b>4928</b>	<b>7096</b>
Sextupole, long	SD	4		4500	4300	1.01	11.7	86	1.1	95	1111	1344	4444	5377
Sextupole, long	SF	2				1.01	11.7	86	1.1	95	1111	1344	2222	2689
<b>Total</b>		<b>6</b>											<b>6666</b>	<b>8066</b>
Octupole	OF1-2	2	0.1			0.30	3.2	94	1.2	113	426	613	852	1226
<b>Total</b>		<b>2</b>											<b>852</b>	<b>1226</b>

**27** Total PS power for **one cell** for main electromagnets **30.3** **41.1**  
KW KVA

	magnet	coils	type
corrector AC+DC (5 independent coils)	3	5	AC+DC
Sextupole, short correctors	6	6	DC

Total number of coils/cell **51**

About 1000 DC-DC low voltage converters: the average channel power is around 1kW and a maximum of 2.3kW.

The stability requested will be 15ppm with a MTBF of more than 400 000 hours.

The integration in 32 cabinets will be designed with the Computer Services for redundancy and **HOT-Swappability**


# GIRDER DESIGN, THE ORTHOGONAL HEPTAPOD



**Mass:**  
Magnets: ~ 5-6 T  
Magnet supports: ~ 1 T  
Girders: ~ 3-3.5 T  
Vacuum chamber, pumping etc: ~ 0.5T  
Total weight: ~9-11T

**Quantity : 128**  
**Procurement time scale: 2016-2017**

**Technology:**  
Girder material:  
carbon steel  
Typical tickness:  
30mm (20-50)  
Piece junction:  
full penetration and  
continous welding  
Rails flatness:  $\pm 30$   
micrometers




**4 motorized adjustable supports in Z direction  
3 manual horizontal jacks (one in X, two in Y)**

**Filippo Cianciosi**


# GIRDER PROTOTYPE TESTS



Girder prototype with dummy magnets:  
Mechanical tests



Courtesy of ISDD-MEG & TID-ALGE



Fully assembled Girder

First vibrational mode at 40 Hz

Virtually no amplification of natural ground motion

# OVERALL PLAN STRATEGY


- All actions sequenced as much as possible
- Design phase nearly completed
- Procurement phase has started
- Assembly overlaps with procurement
- About 3 months time contingency for procurement phase
- About 3 months time contingency for assembly
- About 3 months time contingency for installation
- About 3 months time contingency for commissioning

**ExpD will contribute to:**

- Assembly
- Installation

# EBS MASTER PLAN (2015-2020)

## Master Plan and Major Milestones






# GIRDER ASSEMBLIES


128 girders, 10-12t each

Girders 1 and 4




Girders 2 and 3

All girders will be fully assembled before starting the shutdown for installation




# SYSTEM INTEGRATION – MACHINE LAYOUT IN THE TUNNEL



**Installation: Tunnel Final Layout**

Courtesy :J Guillemin

# BUILDINGS FOR THE ASSEMBLY PHASE



All the girders will be assembled in B1 (Sep 2017-Oct 2018) and stored mainly in the Chartreuse building before the Long Shut-Down




# ASSEMBLY BUILDING LAYOUT



front view


Main facade B1



side view

Principal cutting of B1


top view



Courtesy of TID-BIG

# EBS PROJECT COMMUNICATION

EBS Blog:  
[www.esrf.fr/ebs](http://www.esrf.fr/ebs)



**ALFRESCO Document Management  
is accessible to all  
from the intranet:  
Applications – Alfresco Share**

ESRFlash



Courtesy of A.Joly & Communication Group

## EBS officially started on January 1<sup>st</sup> 2015

### Planned project execution progression:

- 20% completed by the end of 2015: Engineering Design
- 40% expected to be completed by the end of 2016: Delivery of Preseries components
- 60% by the end of 2017: Delivery of >50% of components
- 80% by the end of 2018: Completion of the Assembly
- 100% by the end of 2019: Completion of Installation

**Many thanks to all the ESRF staff for the great enthusiasm, support and achievements...**

**And looking forward for the very exciting work ahead of us.**



MANY THANKS FOR YOUR ATTENTION

