

# Progress Towards the Development of the nEDM@SNS Experiment

Brad Plaster, for the nEDM@SNS Collaboration

University of Kentucky and Oak Ridge National Laboratory

Deputy Experiment Manager PSI 2022 – 19 October 2022

ORNL is managed by UT-Battelle, LLC for the US Department of Energy







### Overview of nEDM@SNS

Experiment under construction at the Spallation Neutron Source at Oak Ridge National Laboratory

Based on the pioneering concept of R. Golub and S. K. Lamoreaux, Phys. Rept. 237, 1 (1994)

 0.5 K Superfluid <sup>4</sup>He Environment
 In-situ UCN production (8.9 Å cold beam)
 Dilute mixture of polarized <sup>3</sup>He as co-magnetometer and spin analyzer
 Large electric field breakdown strength

Projected 90% CL Sensitivity

nEDM@SNS

"Free Precession":  $5.7 \times 10^{-28}$  e-cm

"Dressed Spin":  $2.9 \times 10^{-28}$  e-cm





2

OAK RIDGE

#### Review of Concept: "Free Precession"

Transfer polarized <sup>3</sup>He to measurement cells

Illuminate measurement cells with polarized 8.9 Å beam to produce polarized UCN

Apply  $\pi/2$  pulse to rotate <sup>3</sup>He and UCN spins

Measure precession frequencies via scintillation light and SQUID pickup loops

Remove (de)polarized <sup>3</sup>He from measurement cells





#### Review of Concept: "Dressed Spin"

Transfer polarized <sup>3</sup>He to measurement cells

Illuminate measurement cells with polarized 8.9 Å beam to produce polarized UCN

Apply  $\pi/2$  pulse to rotate <sup>3</sup>He and UCN spins

Apply perpendicular  $B_{\text{RF}}$  field

Control of spins

Remove (de)polarized <sup>3</sup>He from measurement cells



Apply a perpendicular B<sub>RF</sub> field to "dress" the <sup>3</sup>He and UCN spins

 $\mu^{\rm eff} = \mu J_0 (\mu B_{\rm RF} / \omega_{\rm RF})$ 

Precess at same rate at "critical dressing". Control of initial angle and thus scintillation rate (sensitivity).





### Sensitivity Projection: Physics Parameters

# Stated sensitivity projections based on these physics parameters:

**Table 1**. Experimental design goals for the key parameters that influence the statistical uncertainty.

Quantity	Definition	Value	
PUCN	UCN production rate	0.31 UCN/cc/s	
No	Number of UCNs in each cell at t=0	4.5x10 <sup>5</sup>	
V <sub>cell</sub>	Measurement cell volume	3000 cc	
$ au_{eta}$	$\beta$ -decay lifetime	880 s	
τ <sub>3</sub>	UCN- <sup>3</sup> He absorption time	500 s	
$ au_{cell}$	UCN-wall absorption time	2000 s	
E	Electric field	75 kV/cm	
T <sub>m</sub>	Measurement time	1000 s	
T <sub>f</sub>	Cold neutron fill time	1000 s	
T <sub>d</sub>	Dead time between cycles	400 s	
P <sub>3</sub>	<sup>3</sup> He initial polarization	0.98	
Pn	UCN initial polarization	0.98	
$ au_{P}$	<sup>3</sup> He & UCN depolarization time	20,000 s	
83	Detection efficiency for UCN- <sup>3</sup> He capture	0.93	
εβ	Detection efficiency for β-decay	0.5	
Ńв	Non $\beta$ -decay background rate	5 Hz	
	Operatina Pressure	2 atm	

<u>Free Precession</u>:  $\sigma_d \sim \frac{\sqrt{2}\hbar}{4|\vec{E}|\tau P_{He3}P_n\sqrt{mN}}$ 

90% CL ~ 5.7 × 10<sup>-28</sup> e-cm (300 live days) Sinusoidal Scintillation Rate

Dressed Spin:

$$\sigma_d^{\text{tot}} = \frac{\hbar \bar{\tau}_3}{(2J_0|E|N_0\epsilon_3\sin\phi_0) \left\{ \int_0^T \frac{P^2 t^2 e^{-\Gamma t} dt}{\dot{N}_B e^{\Gamma t} + N_0 \left[\frac{\epsilon_\beta}{\tau_\beta} + \frac{\epsilon_3}{\bar{\tau}_3}(1 - P\cos\phi_0)\right]} \right\}^{\frac{1}{2}}.$$

90% CL ~ 2.9  $\times$  10<sup>-28</sup> e-cm (300 live days) Can Optimize the Scintillation Rate





Complete sensitivity details in: M.W. Ahmed et al., JINST 14, P11017 (2019)

### Sensitivity Projection: Management and Current Status

Description of Scope	KPP	NPP	UPP
Magnetic Field Gradient < $\partial B_i / \partial x_j >_{vol} [\mu G/cm]^A$	0.5	0.25	0.1
Magnetic Shielding Factor at 0.01 Hz <sup>A</sup>	1 ×10 <sup>4</sup>	5 × 10 <sup>4</sup>	7.5 × 10 <sup>4</sup>
UCN Wall Loss Time <sup>B</sup>	100	1000	2000
(Photoelectrons) per n- <sup>3</sup> He Capture <sup>C</sup>	6	20	20
SQUID Noise [fT / √Hz] <sup>D</sup>	20	10	1
Electric Field [kV/cm] <sup>E</sup>	10	40	75
<sup>3</sup> He ABS Flux [s <sup>-1</sup> ]   Signal-to-Noise Ratio <sup>F</sup>	1 ×10 <sup>14</sup>   20	1 ×10 <sup>14</sup>   50	1 ×10 <sup>14</sup>   100
<sup>3</sup> He Injection Volume Temperature [mK] <sup>G</sup>	350	320	300
8.9 Å Neutron Flux [n/Å/cm²/s/MW] <sup>H</sup>	2 ×10 <sup>6</sup>	6 ×10 <sup>6</sup>	6 ×10 <sup>6</sup>
8.9 Å Neutron Polarization [%] <sup>H</sup>	80	90	98
Estimated Sensitivity [10 <sup>-28</sup> e-cm] <sup>1</sup>	30	11	3

Present Values \* 0.1  $\mu$ G/cm 5 × 10<sup>4</sup> 800 - 1800 s 17 1.6 fT/ $\sqrt{Hz}$ 75 kV/cm 1 × 10<sup>14</sup> | 20 120 mK 6 × 10<sup>6</sup> n/A/cm<sup>2</sup>/s/MW 87% 6 × 10<sup>-28</sup> e-cm

\* Best estimates based on work to date (i.e., not all measured under experiment's final operating conditions)

KPP: Key Performance Parameter NPP: Nominal Performance Parameter UPP: Ultimate Performance Parameter

CAK RIDGE

nEDM@SNS

#### Experiment Timeline

Rigorous project management process in place with hands-on oversight by the funding agencies (DOE and NSF) and review panels

Most recent bottom-up schedule update projects completion of the project in late-2027 (i.e., apparatus commissioned, all performance parameters on previous slide demonstrated)



However, this schedule assumed construction of the EB-2 Building starting in 2023

We are now planning, in close communication with the funding agencies, for construction of the EB-2 Building to start in 2024. We are currently evaluating the impact of this delay to the EB-2 construction on the overall schedule for project completion.



#### Previous Major R&D Progress: Pre-2021

1/5-Scale High Voltage System Achieved 85 kV/cm with PMMA Electrodes with Copper Implantation



High Voltage Studies Revealed Key (Area) Scaling Laws



#### 1/3-Scale Magnet System Demonstrated Field Gradient Requirements



Measured 1800 s UCN Wall Loss Time in Cryogenic Environment



<sup>3</sup>He System Constructed Full-Scale Non-Magnetic Dilution Refrigerator





Light Collection Prototype Extrapolates to 17 PE in Final Apparatus



## Recent Technical Highlights: Magnetic Fields



3-axis fluxgate (blue) vs. Cryoprobe Array

#### Full-Scale Magnetic Field Performing to Design

nEDM@SNS Slide Content: B. Filippone et al.

**CAK RIDGE** 



#### Recent Technical Highlights: Central Detector



We can now predict the breakdown field distribution for electrodes with arbitrary surface field distribution.

$$P_{S} = \prod_{E_{i}} e^{-S(E_{i})W(E_{i})}$$

The plot on the left assumes that the electrode surface for SNS nEDM is similar to that for electropolished stainless steel. The pressure dependence is taken from our data on mechanically polished electrodes. This plot is for the MC Electrodes and Cavallo combined. Probability of Breakdown at 75 kV/cm Predicted to be Very Small; Further Mitigated by Operating at a Nominal Pressure of 2 Atm

N.S. Phan et al., J. Appl. Phys. 129, 083301 (2021) Slide Content: T. Ito et al.







### Recent Technical Highlights: <sup>3</sup>He Services

. Completion and commissioning of the DR – essentially complete

 Fabricate/assemble/test injection system components – the current phase

- Use test-stand vacuum system and top flange.
- Includes in situ "High field" wall depolarization testing.
   Helding field coile MECP
- Holding field coils, MEOP <sup>3</sup>He polarization.
- Fabricate/assemble/test purification svstem components
  - Requires ORNL top flange, "extended" DR vacuum can.

**CAK RIDGE** National Laboratory



- "Real beam line" including ABS interface.
- Check heat flush transport to test volume.



- . Low-Field Polarization Testing at ORNL
  - Segmented vacuum chamber, SQUID polarization measurement, spin-transport coils



Slide Content: D. Beck, S. Williamson, et al.

\* Metastability Exchange Optical Pumping

Dilution Refrigerator and Test Stand at Illinois







#### Atomic Beam Source

#### Recent Progress:

- Film burner constructed
- Heat flush with Nuclepore filter ready to be installed
- Injection volume complete
- Interim (MEOP\*) source of polarized <sup>3</sup>He for depolarization testing in injection volume



nEDM@SNS

\* Systematic and Operational Studies

# Recent Technical Highlights: SOS\* at PULSTAR

"Mini" nEDM@SNS with one measurement cell, no E field

Small size, rapid thermal cycling

Develop spin manipulation techniques, characterize geometric phase, validate measurement cells





Significant Technical Progress on SOS; Please See Poster by Tom Rao

## Recent Technical Highlights: Magnetic Shield Enclosure

External Coils for Shielding Factor Measurement



nEDM@SNS



Interior: 4.1 m x 4.1 m x 6.1 m

Two 3.0-mm layers of  $\mu$ -metal separated by 40 cm

Layers composed of 0.745 m x 0.3 m x 1 mm sheets tiled to minimize gaps





Within 1 m<sup>3</sup> "Target Volume" centered on location of measurement cells, specifications of |B| < 10 nT and  $dB_i/dx_i < 2$  nT/m largely achieved



### Forward Looking: Strategy for Some Technical Challenges

High electric field R&D program for the nEDM@SNS experiment

T. M. Ito<sup>\*1</sup>, M. A. Blatnik<sup>2</sup>, S. M. Clayton<sup>1</sup>, C. M. O'Shaughnessy<sup>1</sup>, N. S. Phan<sup>1</sup>, and G. V. Riley<sup>1</sup>

> <sup>1</sup>Los Alamos National Laboratory <sup>2</sup>California Institute of Technology

> > December 13, 2021

Scaling Laws for PMMA-Coated Electrodes

Long-Time Testing of PMMA-Coated Electrodes to Establish Mean Time to Failure

Test Full-Scale Cavallo High-Voltage Amplification System in Liquid Helium at Voltages Required for Final Apparatus









"Polarization/Transmission" Test

First beam for nEDM@SNS !

Polarized cold neutrons sent through cryogenic magnets system to verify transmission and polarization

#### Please See Poster by Kavish Imam

#### Collaboration

#### Collaboration Meeting, July 2022





20 US institutions, Simon-Fraser (Canada) and U. Nacional Autónoma de México 67 Voting members of collaboration = significant fraction of research effort on nEDM@SNS 17 current graduate students, 10 current postdocs



#### Acknowledgments and Summary



We are grateful to the funding agencies for their continued commitment to the nEDM@SNS experiment. We thank the many review panels for their expert guidance.

The collaboration is working hand-in-hand with the funding agencies to deliver the experiment on schedule.

Strategies for addressing technical challenges have been vetted by expert review panels.

The next several years will be very exciting for nEDM@SNS!



#### Conclusion: For nEDM@SNS, Our Continued Excitement !





William Cairncross, Jun Ye Nature Rev. Phys., Volume 1, pg 510–521 (2019)