

D. M. Araujo, B. Auchmann, A. Brem, M. Colin, M. Daly and T. Michlmayr

Status of PSI Nb $_3$ Sn Subscale Stress-Managed Common Coils Magnet

2nd joint common-coils meeting, August 2023

This work was performed under the auspices of and with support from the Swiss Accelerator Research and Technology (CHART) program (www.chart.ch).



- Goals and Parameters
- 3D Coil ends optimization
 - 2D vs 3D field quality
 - 3D optimization
- Progress on the engineering design
- Ongoing trials and modelling
- Planning



Subscale Stress-managed Common-coils Goals and Parameters

 The subscale magnet serves as a platform for validating design and optimization tools, as well as manufacturing and assembly processes.

Goals		
Nominal Field B0	4 +	т
T operational	4.5	К
Max current	10.0	kA
Margin at Top and B ₀	> 15	%

Cable & strand (LBNL Subscale CCT)

Strand dia	0.6	mm
Number of strands	11	-
Bare dimensions	3.7 x 1.1	mm
Insulation thickness	0.155	mm
Cu/no-cu	1.17	

Dimensions		
Straight-Section	150	mm
Bore radius	22	
Intra-beam	120	
Total length	350	



2D Magnetostatics: $B_0 = 4.5$ T, I = 7.1 kA

• Peak field on conductor: 5.49 T

• Margin at 4.5 K: 15 %







3D Field Quality Computation

• 1 m and 150 mm long straight section



Multi-poles				
-	2D	3D 1 m	3D 0.15 m	Integral
b3	-0.2	-0.62	-0.26	87.8
b5	-3.1	-3.34	-3.35	-1.2
b7	3.8	3.81	3.82	2.0
b9	-1.	-1.00	-1.00	-0.7
a2	0.9	0.89	-9.54	315.1
a4	3.7	3.71	3.72	5.67
a6	-0.2	-0.23	0.23	-0.8
a8	0.0	-0.01	-0.01	-0.1
		Cross-se	ction	Needs

optimization

Why does the sign of the integral change? 1/2





Why does the sign of the integral change? 2/2







In order to optimize, how can we quickly calculate the integral?





Blocks' contribution and displacement





Optimization scheme















Blocks 2&8: increasing their length would shift the entirely coil pack

Blocks 0&1: increasing their length helps but they contribute little to B1

Blocks 7&13: increasing their length increases this block length but not the whole magnet



Optimization scheme 2



Result 2: sum of multi poles = 15.76





Blocks 0&1 2&8 3&9 4&10 5&11 6&12 7&13



Multi-poles	Units	
-	Cross-section	Integral
b3	0.6	4.3
b5	8.6	5.3
b7	4.2	2.8
b9	- 0.8	-0.6
a2	- 35.4	-3.2
a4	11.3	-3.7
a6	-1.0	-0.3
a8	0.2	-0.3

Optim 2



• T. Michlmayr



Ongoing magnet structure trials and modelling

• Assembling

• Welding trials



• 3D mechanics





Planning: June 2023 version

Tack	July				Aug	ust			September			October						Nove	mbe	r		Dec	embe	er	January						Febr	uary			
Task	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	1	2	3	4	5	6	7	8	9
Engineering Design																																			
Procurement of Coil																																			
Components																																			
1st Coil Ceramic coating																																			
and winding																																			
1st Coil HT																																			
1st Coil Intrumentation																																			
2nd Coil Ceramic coating																																			
and winding																																			
2nd Coil HT																																			
2nd Coil Intrumentation																																			
1st and 2nd Coils splice																																			
and impregnation																																			
3rd Coil Ceramic coating																																			
and winding																																			
3rd Coil HT																																			
3rd Coil Intrumentation																																			
4th Coil Ceramic coating																																			
and winding																																			
4th Coil HT																																			
4th Coil Intrumentation																																			
3rd and 4th Coils splice																																			
and impregnation																																			
Coils Outer Splices																																			
Magnet Structure: intrumentation																																			
Magnet Structure: assembly with																																			
dummy Coils																																			
Magnet Assembly and Final																																			
Checks																																			
Shipment																																			
Jun-23				Thon	nas Ho	lidays					MT 28							HF M			C	AS				Break							F	Page	18