

THE GEORGE
WASHINGTON
UNIVERSITY

WASHINGTON, DC

MUSE Update

Evangeline J. Downie
MUSE Collaboration




GW current awards:
PHY-1614850, 1714833



The Proton Radius Puzzle: Are We Still Puzzled?

- Plot shown at BVR 48:




The Proton Radius Puzzle: Are We Still Puzzled?

Spectroscopy of electronic Atoms and Ions:

- NPL, London: 2S-6S/D in atomic hydrogen
- MPQ, Garching:
 - 2S-4P in atomic hydrogen
 - 1S-3S in atomic hydrogen
 - He⁺ (in preparation)
- LKB, Paris: 1S-3S atomic hydrogen
- YU, Toronto: 2S-2P „Lamb shift“
- VU, Amsterdam: He⁺ (in preparation)
- NIST, Gaithersburg: highly charged ions

Spectroscopy of exotic atoms:


- ETH, Zurich (in preparation):
 - positronium (e⁺e⁻)
 - muonium (μ⁺e⁻)
- PSI, Villigen: μHe⁺



New Radius Result: MPQ

Beyer *et al.*
 Science **358**, 79-85 (2017)
 6 October 2017


N.B.
 5 σ Rydberg deviation required




New Radius Result: Orsay

Hélène Fleurbaey,
 “Frequency metrology
 of the 1S-3S transition of
 hydrogen: contribution to
 the proton charge radius
 Puzzle,”
 Université Pierre et Marie
 Curie (UPMC), 2017,
<https://tel.archives-ouvertes.fr/tel-01633631>

N.B.
 Agrees with Rydberg




Physics Update: The Need for MUSE



MUSE

$\theta \approx 20^\circ - 100^\circ$
 $Q^2 \approx 0.002 - 0.07 \text{ GeV}^2$
3.3 MHz total beam flux
 $\approx 2 - 15\% \mu$'s
 $\approx 10 - 98\% e$'s
 $\approx 0 - 80\% \pi$'s






Beam Hodoscope


Parameter	Performance Requirement	Achieved
Time Resolution	<100 ps / plane	✓ 80 ps
Efficiency	99%	✓ 99.8%
Positioning	≈1 mm, ≈1 mr	not attempted; easy – calibrated by data
Rate Capability	3.3 MHz / plane	✓ >10 MHz / plane

- ❑ Two planes constructed, two will be built in Spring
- ❑ Four planes @ 210 MeV; 3 @ 153 MeV; 2 @ 115 MeV
- ❑ SiPMs radiation damage tested – not problematic


Beam Hodoscope



Beam Hodoscope – November 2017



GEM



Parameter	Performance Requirement	Achieved
Resolution	100 μm / element	✓ 70 μm
Efficiency	98%	✓ 98%
Positioning	≈ 0.1 mm, ≈ 0.2 mr	planned
Rate Capability	3.3 MHz / plane	✓ 5 MHz
Readout Speed	2 kHz / 20% deadtime	1.5 kHz / 100% deadtime

Target

Parameter	Performance Requirement	Achieved?
Liquid hydrogen	maintain liquid hydrogen-filled cell at $T \approx 19$ k and $P \sim 1$ atm	not attempted; moderate
Cool down time	< 3 days	✓ achieved; < 2 hours!
Beam entrance window	> 6 cm	✓ achieved; easy
Exit window(s) (One continuous or two symmetric on beam left and beam right)	$20^\circ < \theta < 100^\circ$; $\phi = 0^\circ \pm 45^\circ$ at $\theta = 60^\circ$ beam up-down and beam left-right symmetry	✓ achieved; challenging

Target


final LH₂ cell
at $\Delta P = 2$ bar & 77 K




Target ladder connected
to lifting lid




After full
integration





Chamber being
leak tested



Target Cool-Down Curve from 12.02.2018!






Straw Tube Tracker



GenFit: 120 μ m residuals

Parameter	Performance Requirement	Achieved
Position Resolution	150 μ m	✓ <120 μ m
Efficiency	99.8% tracking	≈ 99% in prototype; moderate
Positioning	≈0.1 mm, 0.2 mr in θ	not attempted; moderate
Positioning	≈0.5 mr pitch, yaw, roll	not attempted; moderate
Positioning	50 μ m wire spacing	✓ 35 μ m achieved in dress rehearsal
Rate Capability	0.5 MHz	✓ achieved in dress rehearsal

Straw Tube Tracker




Scattered Particle Scintillators


Parameter	Performance Requirement	Achieved
Time Resolution	≈ 60 ps / plane	✓ 55 ps
Efficiency	99%, \ll 1% paddle to paddle uncertainty	✓ 99%, paddle to paddle not attempted, moderate
Positioning	≈ 1 mm, ≈ 1 mr	not attempted; easy
Rate Capability	0.5 MHz / paddle	✓ 1 MHz

Scattered Particle Scintillators

- ❑ One complete side mounted at PSI
- ❑ Time resolution exceeds requirements:
 - ✓ σ (front) < 50ps
 - ✓ σ (rear) < 60ps




Scattered Particle Scintillators



SPS Right Front and Rear Walls
mounted at PSI, December 2017

Beam Monitor


Parameter	Performance Requirement	Achieved
Time Resolution	< 100 ps / paddle (bar)	✓ 60 ps (30 ps)
Efficiency	99%	✓ 99.8%
Positioning	≈ 1 mm, ≈ 1 mr	not attempted; easy
Rate Capability	3.3 MHz / plane	not attempted; easy




Beam Monitor Scintillators




Time resolution measured at USC



Beam Monitor Thin Scintillator SiPM Detectors



	SiPM	σ_T	Efficiency
1	S13360-3075PE	59 ps	99.9%
2	S13360-3050PE	60 ps	99.7%
3	AdvanSiD	65 ps	99.0%



Front STT

GEMs

Beam Hodoscope

Quads

2x2

Table

Guy—temporary installation

Beam Monitor



Scintillator Walls

In 2018 we plan to assemble the full experiment

Crane-able Platform

Total Deflection [mm]




A: Static Structural
Total Deformation
Type: Total Deformation
Unit: mm
Time: 1



- Design by Argonne
- Passed stress analysis

Stress in Plates [MPa]

A: Static Structural
Equivalent Stress
Type: Equivalent (von-Mises) Stress
Unit: MPa
Time: 1
Custom Obsolete



MUSE Beamtime Request: Inputs

- ❑ Long term MUSE request: 12 months of production data
- ❑ Moderate confidence we can be ready July 1st 2018
 - Limiting factor: new STT readout card production timeline
 - ***Should have more certainty by April 15th***
- ❑ Studied MUSE installation / de-installation
 - Remove MUSE platform from the hall: **3 days**
 - Move MUSE into the hall and get ready to take beam: **14 days** (including target cool-down and straw alignment measurement)

MUSE Beamtime Request: Conclusion

- ❑ Plan: set up MUSE on platform in PiM1 April – June 2018
- ❑ Requested and preferred (single installation):
 - July 23rd: 2 wks reinstallation + 2 wks of debugging time
 - September 1st: 4 months of production data
- ❑ Alternate scenario (assumes already set up in PiM1):
 - July 1st: 2 wks of debugging time + 2 wks test data
 - September 1st: 2 wks reinstallation + 3.5 months of production data
- ❑ Lose ≥ 15 days each installation / de-installation cycle