

TC status & plan

April 5, 2018

Yusuke Uchiyama



TC condition in RUN2017

- Bad channels
 - TC origin (SiPM or backplane): 1 channel showed current overflow
 - WD connectors: several channels on 4 boards.
Noisy, unstable → apply temporary grounding. One connector completely detached.
- No laser signal
 - 11 counters (2 in US, 9 in DS).
- Temperature controlled at 20°C by chiller system
 - Use chiller devices used for MEG TC.
- Operation voltage determined by bias scan of laser run.
 - Best time-resolution point on average (not optimized counter-by-counter) → +1 V.
 - Reduce voltages on high current channels.

Maintenance

Items to be done

1. Investigate and repair the broken fibers (9 counters in DS, 2 in US)
2. Investigate and replace bad counters (1 dead ch, 1 high current)
3. Fix broken laser tube
4. Replace broken cables
5. Fix problematic thermometers
6. Check SiPM detachment for picked up samples

Maintenance

Items to be done

Mitsutaka& Yusuke


1. Investigate and repair the broken fibers (9 counters in DS, 2 in US)
✓ Done for US. 2 of DS ones fixed by reconnection, 7 were picked up.
2. Investigate and replace bad counters (1 dead ch, 1 high current)
✓ The two counters (DS) were picked up.
3. Fix broken laser tube
✓ Done
4. Replace broken cables
✓ Done. 3 spare cables at each side were additionally installed.
5. Fix problematic thermometers
✓ Ongoing. Spare sensors are under preparation in Genoa.
6. Check SiPM detachment for picked up samples
✓ Done. 4 picked-up counters were checked and found **no detachment**.

US is ready in perfect condition. We'll resume maintenance of DS in April.

Chiller upgrade

Matteo

- One of the chillers was broken.
 - Just after the run finished, coincident with a power cut.
- New powerful chillers bought by GE group
 - 400 W → 1 kW
 - one for each sector
 - larger dimensions → place in the area to be discussed.
 - one of them has been delivered to PSI.
- Flow control using valves
 - Under test in Genoa.
 - Control system/algorithm to be implemented.
 - SCS3000 or standalone?



Cooled dry air

Masashi


- We aim at 10°C operation
 - to reduce the SiPM performance degradation due to radiation damage.
 - Humidity control is required to avoid water condensation.
- Flushing dry air turned out an effective solution.
- But, controlling the temperature is necessary
 - for stability & uniformity of temperature of the TC volume.
- Basic idea will be discussed in this meeting.
 - Need test and engineering this year.

Laser system upgrade

- Optical switch was finally delivered.
 - Change manufacturer from Piezo → LEONI.
 - 1×12 for 8 output fibers.
 - Control via SCS3000 (implemented).
- Controllable optical attenuator
 - to control laser power.
 - Bought.
 - To be tested at PSI.
- Replace SYNC cable with temperature-insensitive one.

Massimo

Mitsutaka



We can control everything remotely this year.

Survey


Mitsutaka

- Perform 3D scan of DS
 - Analysis of US data ongoing.
 - Move DS TC outside piE5.
- Modify the reference points on DS for laser tracker.
 - Original points were hard to see with the end-cap.
 - To be discussed with survey group.

Production of spare counters

- Now we have scant spare counters.
- Additional 198 SiPMs were bought by PV group (recently, +40 for spare of spare).
 - Different (new) type from existing counters' one
 - Different electrical characteristics:
 - Breakdown voltage larger by 2 V
 - Wider operational range
 - ⇒ Different operational voltage (+18 V),
cannot be used mixed with others in a WDB.
- Have to replace 8 counters as a set.

Paolo



- Plan:
 - Make 8 40-mm counters & 8 50-mm counters this summer.
 - Install them in **the next shutdown** at important/high-hit-rate location.
 - Picked up 8+8 counters will be used as spares of existing counters.

Analysis

- Analysis of RUN2017 data in progress.
- Performance was already presented in Jan.
- Background study.
 - Hit distribution, hit rate
 - comparison with MC
 - Study impact of beam displacement
- Calibration
 - Further study both for laser & Michel.
 - Application to the data, used in official reprocesses.
- Radiation damage effects
 - Damage unbalance.

Miki

Mitsutaka

Masashi

Data-taking this year

Before installation

- Laser
 - want to test the new components before installation.
 - need at least two crates.

May–Jul

After installation, after WDBs for LXe gets ready?

- C–W boron ?
 - worth trying with full acceptance of LXe.
- Dalitz in CEX ??
 - not clear how much useful w/o CDCH.
 - Neutron irradiation to be cared. (shorter beam time is better)
- Mott ???
 - Last years experience shows Mott positron DAQ is difficult with MEG II setup.
 - Much higher BG rate. Due to material at downstream? Understandable?
 - Without detailed study (MC of Mott beam?), reluctant to do it again.
 - US is better?

Oct

Nov?

- WD **crates assignment**
 - to be considered including CDCH test.
 - Location of crates is an issue.
 - TC requires crates in central racks at bottom position.
 - CDCH? Cable length limitation?
- **DAQ rate** is also an important factor
 - with DCB and new MEGON
 - but also with much increased number of channels.
- Muon beam run
 - want to occupy 4 crates continuously
 - to avoid inefficient and dangerous re-cabling works as last year.

Dec

Conclusion

- TC will be final & perfect condition this year
 - US maintenance completed, DS soon.
 - Several upgrades planned.
- Waiting for the engineering run & physics run
 - Anticipating data taking with CDCH this year.

Extraction from COBRA

thanks to Manuel

- Both TCs were extracted from COBRA on 6th Feb. (on schedule)
 - We broke 3 signal cables during the work.
 - We checked all channels for current and laser signal and found no additional bad channels
- After the extraction,
 - TCs will stay in piE5 area for the maintenance work till next installation.
 - We won't unplug signal cables from TC nor optical fibers from the splitter boxes.



April 1 2018 08:27:20 010 18:42:57

YUSUKE UCHIYAMA

