



Gian Luca Orlandi :: Electron Beam Instrumentation

Electron instrumentation

3rd SwissFEL Performance Workshop

January 27, 2021





- Progress in 2020:
 - DWCM: upgrade of IOC/Channels recording B1&B2 signal at 100Hz (Divall, Voulot, O.)
 - DICT: upgrade to independent trigger for B1&B2 (Llorente)
 - DICT: Save&Restore procedure of the settings, also applying to DBLM and DLLM (Llorente, Alarcon, O.)
 - Meas. campaign (DWCM,DICT,DBPM vs FC) for absolute charge calibration (Craievich,Marcellini, O.)
- Present status:
 - DICT (Aramis&Athos) in operation (100Hz, B1&B2)
 - DICT calibration: last measurement session on 17.01.2021. Data analysis on-going
 - Charge calibration campaign (DFCP,DICT,DWCM,DBPM): results to be presented in a SPM in February
- Issues:
 - Aramis DICTs show a relative systematic discrepancy, fortunately constant over a long time scale (~1 year)
- Plans/Upgrades:
 - DWCM (Summer 2021): Summer Student Position for characterization of the transfer function in the frequency and time domain and studies of possible improvements
 - DICT: according to the calibration results, decision has to be taken whether :
 - live with a systematic error and off-line correction;
 - investigate and fix the problem (new project and new resources, Porthos 3-bunch upgrade could be the right framework);
 - think of calibrating the existing DWCM and the spare one (to be possibly installed at the high energy section of the machine) for absolute charge measurements and BAG issues.



- Progress in 2020:
 - DDRM:
 - Maintenance DDRM-SATUN22→19
 - New installation: DDRM-SATUN18→8
 - Set-up reshuffling for additional sensors (not in the HL-Liste) SATUN05-DDRM405-R (z=418.5m) and SATUN14-DDRM405-R (z=443.7m)
 - New controller set-up and control panel reshuffling (Divall); additional cabling (Villano)
 - DBLM:
 - SATUN14-DBLM405 & SATUN22-DBLM005 fiber replacement
 - Installation and beam commissioning of SATDI01-DBLM305
 - DLLM:
 - Installation (Baldinger, O.) and beam commissioning of SATUN09-DLLM035 (from z=430m to z=500m)
- Present status:
 - Sensor installation according to the planning
 - Loss monitor signals integrated in the MPS (DBLM and DLLM 100Hz, B1&B2)
- Issues:
 - DBLM Athos undulator set-up judged as very essential
- Plans/Upgrades:
 - SATDI01-DBLM095 (z=344m) and SATDI01-DBLM105(z=346m) to be installed with dechirper (April 2021)

Bunch Compression Monitors (DBCM) System Expert: G.L. Orlandi


- Progress in 2020:
 - hand-over DBCM responsibility from F.Frei in July 2020
 - Reliable and well structure legacy from Franziska
- Present status:
 - SINBCO2-DBCM410:
 - integrated in the machine compression feedback (100Hz, B1&B2)
 - SARMA01-DBCM030:
 - ready to be integrated in the machine compression feedback (100Hz, B1)
 - S10BCO2-DBCM410:
 - HW to be installed/commissioned first
 - IR-Hutch infrastructure complete
 - continued only if requested by project.
- Issues:
- Plans/Upgrades:
 - SARMA01-DBCM030 spectrometer maintenance






Coherent Diffraction Radiator (DCDR)

System Expert: G.L. Orlandi



- Progress in 2020:
 - Hand-over DCDR responsibility from F.Frei in July 2020
 - Reliable and well structure legacy from Franziska
- Present status:
 - S10MA01-DCDR080 integrated in the machine compression feedback (100Hz, B1&B2)
- Issues:
 - S10MA01-DCDR080 polarizer set automatically to zero as a system protection action in case of machine interlock (manual setting of the polarizer at the original value needed at the restart)
- Plans/Upgrades:
 - New DCDR Athos SATSY03-DCDR050 ($z=318.5\text{m}$):
 - All components already on place or ordered (with the exception of the Beckhoff Motion+DAQ server)
 - In-vacuum components and optics+detector box planned to be installed in April 2021 shut-down
 - Beam commissioning planned in Summer 2021
 - New DCDR Aramis SARCL01-DCDR105 ($z=449.9\text{m}$):
 - Most of the components already on place or ordered;
 - Time schedule of the device installation not defined yet (reasonably after SATSY03-DCDR050 commissioning)






- Progress in 2020:
 - Update of the WSC-HL-application (A.Gobbo, O.) to 2-bunch operations
 - Athos DWSCs commissioned with beam
 - Phase Space Tomography with Wire Scanner (see next slide)
 - Signature of License Agreement Contract between PSI and UHV-Design for the Intellectual Property Transfer and Commercialization of the SwissFEL WSC (M. Frei-Hardt, P. Heimgartner, O.)
- Present status:
 - WSC emittance measurements performed with pyscan code (adapted from screen meas., E. Prat, P. Dijkstal, A. Babic) and WSC-HL-application (A.Gobbo, O.)
 - Emittance measurements successfully performed after BC1 & BC2 with S10DI01-DWSC010 (z=110m) and SARCL01-DWSC160 (z=452m)
 - Athos switch-yard matching: emittance measurements with SARMA02-DWSC060 (z= 492m) successfully performed

- Issues:

- Emittance measurements with SARCL01-DWSC160: quadrupole scanning interval limited by beam-losses directly driven by optics mismatch blinding the beam losses produced by the wire




- Plans/Upgrades:

- WSC emittance measurements with FODO scheme (in collaboration with BD): WSC set-up ready



PHASE SPACE TOMOGRAPHY WITH WIRE SCANNER—BENEDIKT



- ▶ Spider web wire scanner manufactured by LMN
- ▶ Tomographic reconstruction of the beam shape



Synchrotron Radiation Monitor (DSRM)

System Expert: G.L. Orlandi



- Progress in 2020:
 - Installation of 2-bunch camera (gated MCP) in SINBC02-DSRM310 (M.Baldinger, T.Stapf, O.)
 - 2-bunch camera timing and software configuration (H. Brands)
- Present status:
 - SINBC02-DSRM310: basic commissioning B1&B2 done (timing)
 - S10BC02-DSRM310 in operation (sCMOS camera, 100Hz, reduced ROI)
- Issues:
- Plans/Upgrades:
 - Adapt HL-Screen application to 2-bunch operations
 - Pixel calibration (um) and ROI to be set
 - IOC channel to be configured to lock the camera timing to the beam timing



Pulse Energy Monitors (Gas Detectors)

System Expert: P. Juranić

- Progress in 2020:
 - Aramis UV light issue solved with addition of UV filter in the last DSCR.
 - Athos gas detector commissioned and running successfully, used for all sorts of stuff.
- Present status:
 - Both Athos and Aramis branches in operation.



- Issues:
 - Athos DAQ is not synched correctly. Controls is looking to see where the problem is.
 - Archiver saving of data is unreliable, with the data being lost or format changed. Controls is looking into it.
- Plans/Upgrades:
 - Fast signal absolute energy calibration. Algorithm done, waiting for PV's to be created.
 - Automated gas exchange.
 - Athos gas detector as a rough spectrometer (central energy measurement).



DSCR (Screens)

System Expert: P. Juranić

- Progress in 2020:
 - Likely primary source of poor resolution discovered (filters with poor optical qualities).
 - Alternate filters found, but required a re-design of DSCR to fit different focal lengths.
 - Redesign is finished, parts are ordered. Initial plan is to upgrade SARCL01-DSCR170 und SATBD01-DSCR120 (main ones for emittance measurements).

- Present status:
 - DSCR's in operation and working OK.

- Plans/upgrades:
 - Looking at secondary issues to improve resolution, like non-linearity of scintillators. Investigating thinner scintillators and computational models that correct for it.
 - May want to turn all DSCRs into the better-resolution version.




Abbildung 1: ND 2.0 Film Filter (9,156)




Abbildung 2: without Filter (14,783)



HERO screens

System Expert: P. Juranić

- Progress in 2020:
 - Defined measurement parameters and concept developed to measure e-beam/laser beam time and spatial overlaps.
 - Tests for diode responses to electron-generated OTR light and further tests on possible fine-time measurement tools are ongoing at the ACHIP chamber.
 - Test with laser heater performed to gain experience, look at issues, and try out some new ideas.
- Issues:
 - Parameters may need to change due to the evolving developments with the HERO project, which will require a design change.
 - A bit more HERO-dedicated communication would be welcome to be able to respond to changes more quickly before device drawing and construction starts.
- Plans:
 - Change design to fit new parameters, order parts.

Mit einzigartigen Beschleunigeranlagen an die Spitze der Forschung:
We make science work!

Thank you for your attention

